



Hydronic & Radiant Heating Supplies
www.Blueridgecompany.com

Design
BlueRidgeCompany.com

Email:design@blueridgecompany.com

Radiant Panel Schedule

Project #:007 - George Zule
June 4, 2010

Project Information

Project #: 007 - George Zule
Name: George Zule
Location:

Notes:


Design Conditions and Summary

Floorplans / Levels:
Main Floor 1,908 ft²
Total Area: 1,908 ft²

Radiant Panel Details

Panel Type #1 - Concrete Thin Slab

Over-pour Thickness: 2 in
 Tube Depth: 2 in
 Over-pour Material: Masonry Units - Concretes, cement/lime, mortar, and stucco (100 lb/ft³)
 Over-pour Rv: 0.3 hr-ft²-°F/btu
 Sub-Floor Thickness: 0'-0 3/4"
 Sub-Floor Rv: 0.9 hr-ft²-°F/btu
 Joist Construction: Joist 2"x10" pine, 16" OC
 Joist Spacing: 16 in
 Joist Insulation Rv: 5.4 hr-ft²-°F/btu
 Spacing: 8 in, 9 in
 Floorplans:
 Main Floor 1,768 ft²



Disclaimers

The calculated values shown in this report are based on the data input by the user of the software. Inaccurate or erroneous data input will result in inaccurate or erroneous results. You are strongly advised to review all input data carefully, and to have the calculated results reviewed by an experienced heating professional to ensure reasonableness and suitability for your application.

IN NO EVENT WILL AVENIR SOFTWARE INC. ("AVENIR") OR ITS AFFILIATES BE LIABLE UNDER ANY CONTRACT, NEGLIGENCE, STRICT LIABILITY OR OTHER LEGAL OR EQUITABLE THEORY FOR ANY CONSEQUENTIAL, INCIDENTAL, INDIRECT OR SPECIAL OR PUNITIVE DAMAGES WHATSOEVER (INCLUDING, BUT NOT LIMITED TO, DAMAGES FOR LOSS OF BUSINESS PROFITS, BUSINESS INTERRUPTION, LOSS OF BUSINESS INFORMATION OR DATA AND THE LIKE), EVEN IF SUCH PARTY HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGES. AVENIR'S CUMULATIVE LIABILITY FROM ANY CAUSE RELATED TO OR ARISING FROM THE USE THIS REPORT, AND REGARDLESS OF THE FORM OF THE ACTION, SHALL BE LIMITED TO NO GREATER THAN THE AMOUNT OF FEES PAID TO AVENIR UNDER THE SOFTWARE LICENSE AGREEMENT.